

Product show



1. Une variété de matières premières par un certain pourcentage de mélange, dans la trémie



2. Les matières premières mélangées sont préférées -formées et chauffées pour devenir des tuiles plates



3. Ensuite, à travers la pression du moule, le moulage élastique, le refroidissement, à travers la machine de traction lentement introduite



4. Pour atteindre la longueur des besoins des clients couper. après une sortie artificielle

Cliquez sur [asa fabricant de toiture en pvc chine](#) pour apprendre plus







Purplish Red



Brick Red



Sky Blue











Black



Dark Green

| | | | | | |
|-------------------------|-----------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-------|-------|
| Product name | | ASA Synthetic Resin Roof Tile | | | |
| Material | | ASA(Acrylonitrile Styrene acrylate copolymer)+PVC(Polyvinyl chloride) | | | |
| Type | | Spanish Style | | | |
| Overall Width | | 1050mm | | | |
| Effective Width | | 960mm | | | |
| Thickness | | 2.3mm—3.0mm | | | |
| Length | | Customized(According to the size of container) | | | |
| Color | | Customized | | | |
| Purlin Spacing | | 660mm | | | |
| Thickness | | 2.3mm | 2.5mm | 2.8mm | 3.0mm |
| Weight (kg/SQM) | | 4.6 | 5.0 | 5.6 | 6.0 |
| Container Load capacity | 20 GP (21 Tons) | 4500 | 4200 | 3750 | 3500 |
| | 40 GP (26 Tons) | 5600 | 5200 | 4600 | 4300 |
| Feature | | 1.Excellent Anti-corrosion Performance 2.Good Waterproof Performance 3.Fire Resistance 4.Heat insulation 5.Sound insulation 6.Weather fastness,ageing resistance | | | |
| Package | | Nude or standard export package | | | |

| Item No. | Name | Picture | Item No. | Name | Picture |
|----------|--------------------------|-------------------------------------------------------------------------------------|----------|--------------------------------|---------------------------------------------------------------------------------------|
| 1 | ASA Synthetic Resin Tile |  | 7 | Main Ridge Tile Head |  |
| 2 | Main Ridge Tile |  | | Main Ridge Turnup |  |
| 3 | Tilted Ridge Tile |  | 8 | Four-way |  |
| 4 | Tilted Ridge Tile Head |  | 9 | Left / Right Eave Sealing Tile |  |
| | Tilted Ridge Turnup |  | 10 | Guide Plate Tile |  |
| 5 | Modern eave drip tile |  | 11 | Vertical Wall Flashing Tile |  |
| | Antique eave drip tile |  | 12 | Screw And Hat |  |
| 6 | Three-way |  | | | |

Accessories





Certificate



Foshan Supervision Testing Centre of Quality and Metrology
Test Report

| No. | Item | Unit | Requirement | Result | Verdict |
|-----|---------------------|-------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|-----------|
| 1 | Appearance | — | The color of the sheet is uniform. There should be no bubbles, cracks or visible impurities on the surface. There should be no visible defects on the surface. | Confirmed | Pass |
| 2 | Wall thickness | mm | 0.2 | 0.2 | Pass |
| 3 | Thickness deviation | mm | ±0.02 | ±0.02 | Pass |
| 4 | Density | g/cm ³ | — | 1.170 | — |
| 5 | Tensile strength | MPa | ≥1.0 | 1.0 | Pass |
| 6 | Elongation at break | % | ≥2.0 | 2.0 | Pass |
| 7 | Holding full impact | kJ/m ² | — | — | Confirmed |
| 8 | Char temperature | °C | — | — | Confirmed |
| 9 | Char residue | % | — | — | Confirmed |
| 10 | Flame spread | — | — | — | Confirmed |
| 11 | Flame spread | — | — | — | Confirmed |
| 12 | Flame spread | — | — | — | Confirmed |
| 13 | Flame spread | — | — | — | Confirmed |
| 14 | Flame spread | — | — | — | Confirmed |
| 15 | Flame spread | — | — | — | Confirmed |

Foshan Supervision Testing Centre of Quality and Metrology
Test Report

| No. | Item | Unit | Requirement | Result | Verdict |
|-----|---------------------|-------------------|--------------------------------------------------------------------------------------------------------------------|-----------|-----------|
| 1 | Appearance | — | The surface should be smooth and uniform. There should be no bubbles, cracks or visible impurities on the surface. | Confirmed | Pass |
| 2 | Surface roughness | mm | 0.1 | 0.1 | Pass |
| 3 | Tensile strength | MPa | ≥1.0 | 1.0 | Pass |
| 4 | Elongation at break | % | ≥2.0 | 2.0 | Pass |
| 5 | Flexural strength | MPa | ≥1.0 | 1.0 | Pass |
| 6 | Flexural modulus | MPa | ≥1.0 | 1.0 | Pass |
| 7 | Density | g/cm ³ | — | 1.170 | — |
| 8 | Heat stability | — | — | — | Confirmed |
| 9 | Heat stability | — | — | — | Confirmed |
| 10 | Heat stability | — | — | — | Confirmed |
| 11 | Heat stability | — | — | — | Confirmed |
| 12 | Heat stability | — | — | — | Confirmed |
| 13 | Heat stability | — | — | — | Confirmed |
| 14 | Heat stability | — | — | — | Confirmed |
| 15 | Heat stability | — | — | — | Confirmed |



Our Factory





Our Customer



Packaging



FAQ

* Vous êtes fabricant ou commerçant ?

* Oui, nous sommes un vrai fabricant, il y a beaucoup de photos dans l'introduction de notre société. Si vous avez besoin d'un autre produit spécial, nous ferons de notre mieux pour vous aider, afin que nous puissions établir une relation commerciale à long terme.

* Puis-je commander le produit avec je veux profiler ?

* Naturellement vous pouvez, également nous produisons les produits selon vos demandes de détail.

- * **Pouvez-vous mettre la marque de mon entreprise sur vos produits ?**
- * **Oui, nous acceptons le service OEM & ODM. Mais nous avons besoin d'informations sur votre entreprise.**
- * **Comment installer la tôle de toiture?**
- * **Veillez contacter notre personnel de service, nous avons une vidéo d'installation pour vous.**
- * **Pouvez-vous me fournir des échantillons pour ouvrir le marché et tester qualité?**
- * **Oui, nous pouvons. Nous pouvons vous fournir des échantillons gratuits, pourriez-vous payer les frais d'expédition ? Veillez contacter notre personnel de service.**
- * **Quel est votre terme commercial?**
- * **Paiement : T/T 30 % à l'avance, solde avant expédition.**
- **Délai de production : dans les 7 jours ouvrables après dépôt de 30 %**
- **Port d'expédition FOB : Foshan, Guangzhou, Shenzhen**